

Center Alley - West Main Street to Madison Ave Resurfacing Project  
Village of Ashville, Ohio

REF. NO.	ITEM NO. *	DESCRIPTION	ESTIMATED QUANTITIES	UNIT	UNIT PRICE IN FIGURES						EXTENSION	
					MATERIAL		LABOR		TOTAL SUM OF MATERIAL AND LABOR		TOTAL IN FIGURES	
					\$	".00"	\$	".00"	\$	".00"	\$	".00"
<b>BASE BID</b>												
1	201	CLEARING AND GRUBBING	LUMP	LS								
2	202	PAVEMENT REMOVED & DISPOSED OF	335	SY								
3	252	FULL DEPTH PAVEMENT SAWING (O.D.O.T.)	1015	LF								
4**	253	FULL DEPTH PAVEMENT REPAIR (6" DEPTH)	58	CY								
5	254	PAVEMENT PLANING ASPHALT CONCRETE (3")	1570	SY								
6	407	TACK COAT (APPLIED @ 0.25 GAL/SY)	395	GAL								
7	413	CRACK SEALING, HOT APPLIED	1015	LF								
8	448	1.5" ASPHALT CONCRETE, SURFACE TYPE 1	65	CY								
9	448	1.5" ASPHALT CONCRETE, INTERMEDIATE TYPE 1	65	CY								
10	604	MANHOLE ADJUSTED TO GRADE	2	EA								
11	614	MAINTAINING TRAFFIC	LUMP	SUM								
12	624	MOBILIZATION	LUMP	SUM								
13	608	CURB RAMP	2	EA								
14	609	CURB, STRAIGHT 18'	45	LF								
					ITEMS 1-14		<b>Sub-Total</b>		\$			
15	Spec.	Force Account (.10 x Sum of Items 1 through 14)					<b>Sub-Total</b>		\$			
<b>TOTAL BID (ITEMS 1-15)</b>									\$			
<b>* REFERS TO OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS</b>												
<b>** CONTINGENCY ITEMS, IF AUTHORIZED BY ENGINEER</b>												

The Bidder's Total is for information only at the time of opening bids. The Village will make the extension and if there are differences in the totals, the Unit of Lump Sum Prices shall govern.

Federal I.D. No. \_\_\_\_\_