

APPENDIX B

RESURFACING AND SURFACE TREATMENT SUBSUMMARY

LOCATION	202	204	253	301	448	448	604	608	608	608	609	644	644	644	644
	PAVEMENT REMOVED	SUBGRADE COMPACTION	FULL DEPTH PAVEMENT REPLACEMENT (12" DEPTH)	7.25" BITUMINOUS AGGREGATE BASE	1.25" ASPHALT CONCRETE, SURFACE TYPE 1	1.5" ASPHALT CONCRETE, INTERMEDIATE TYPE 2	MANHOLE ADJUSTED TO GRADE	CONCRETE WALK, 4" THICK	CURB RAMPS	DETECTABLE WARNING, AS PER SUPP SPEC 1551	CURB, 18" STRAIGHT	STOP LINES, 20" WIDE	TRANSVERSE LINE 10" WIDE	PARKING LOT STALL MARKER	HANDICAP SYMBOL MARKING
	SY	SY	CY	CY	CY	CY	EA	SF	EA	EA	LF	LF	FT	FT	EA
CROMLEY STREET	1305	1305	48												
SCHOOL STREET	90	90	4												
MADISON AVENUE	65	65	22												
RUTH PLACE	32	32	11												
HARRISON STREET	48	48	16												
CHERRY STREET	69	69	23												
GARY ALLEY	36	36	12												
POPLAR STREET AND HALL STREET	67	67	22												
RICH STREET	66	66	22												
SOUTH STREET	35	35	12									14			
MAPLE STREET	79	79	26									14			
CHURCH STREET	12	12	4				1								
LEXINGTON AVENUE	63	63	21												
ASHTON VILLAGE PHASE 2	28	28	9												
STATION STREET	62	62	21												
EAST MAIN STREET	40	40	13												
MILLER AVENUE	284	284	95												
VILLAGE HALL		406		51	9	11		1360	2	2	140		280	550	2
WATER PLANT	233				8	10									
TOTALS CARRIED TO GENERAL SUMMARY:	2614	2787	381	51	17	21	1	1360	2	2	140	28	280	550	2

* REFERS TO OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS

GENERAL SUMMARY

DESCRIPTION	ITEM	UNIT	TOTAL
BASE BID			
PAVEMENT REMOVED	202	SY	2614
SUBGRADE COMPACTION	204	SY	2787
FULL DEPTH PAVEMENT REPLACEMENT (12" DEPTH)	253	CY	381
7.25" BITUMINOUS AGGREGATE BASE	301	CY	51
1.25" ASPHALT CONCRETE, SURFACE TYPE 1	448	CY	17
1.5" ASPHALT CONCRETE, INTERMEDIATE TYPE 2	448	CY	21
MANHOLE ADJUSTED TO GRADE	604	EA	1
CONCRETE WALK, 4" THICK	608	SF	1360
CURB RAMPS	608	EA	2
DETECTABLE WARNING, AS PER SUPP SPEC 1551	608	EA	2
CURB, 18" STRAIGHT	609	LF	140
STOP LINES, 20" WIDE	644	LF	28
TRANSVERSE LINE 10" WIDE	644	FT	280
PARKING LOT STALL MARKER	644	FT	550
HANDICAP SYMBOL MARKING	644	EA	2
* REFERS TO OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS			

Village of Ashville
2019 Paving Program

Required

REF. NO.	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	UNIT	UNIT PRICE IN FIGURES						EXTENSION	
					MATERIAL		LABOR		TOTAL SUM OF MATERIAL AND LABOR		TOTAL IN FIGURES	
					\$	".00"	\$	".00"	\$	".00"	\$	".00"
BASE BID												
1	202	PAVEMENT REMOVED	2614	SY								
2	204	SUBGRADE COMPACTION	2787	SY								
3	253	FULL DEPTH PAVEMENT REPLACEMENT (12" DEPTH)	381	CY								
4	301	7.25" BITUMINOUS AGGREGATE BASE	51	CY								
5	448	1.25" ASPHALT CONCRETE, SURFACE TYPE 1	17	CY								
6	448	1.5" ASPHALT CONCRETE, INTERMEDIATE TYPE 2	21	CY								
7	604	MANHOLE ADJUSTED TO GRADE	1	EA								
8	608	CONCRETE WALK, 4" THICK	1360	SF								
9	608	CURB RAMPS	2	EA								
10	608	DETECTABLE WARNING, AS PER SUPP SPEC 1551	2	EA								
11	609	CURB, 18" STRAIGHT	140	LF								
12	644	STOP LINES, 20" WIDE	28	LF								
13	644	TRANSVERSE LINE 10" WIDE	280	FT								
14	644	PARKING LOT STALL MARKER	550	FT								
15	644	HANDICAP SYMBOL MARKING	2	EA								
* REFERS TO OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS												
CONTINGENCY QUANTITIES												
16	203	WEARING COURSE REMOVED (GRAVEL OR ASPHALT)	50	SY								
17	252	PERMANENT PAVEMENT REPLACEMENT, TYPE 1	50	CY								
18	304	AGGREGATE BASE	25	CY								
19	604	STRUCTURE ADJUSTED TO GRADE	2	EA								
								ITEMS 16-19	Sub-Total	\$		
								ITEMS 1-15	Sub-Total	\$		
20	Spec.	Force Account (.10 x Sum of Items 1 through 15)[If Authorized by Engineer]							Sub-Total	\$		
TOTAL										\$		

The Bidder's Total is for information only at the time of opening bids. The Village will make the extension and if there are differences in the totals, the Unit of Lump Sum Prices shall govern.

Federal I.D. No. _____